



TEST CONDITION:

- 1.100% OPEN, SHORT, MISWIRE TEST
- 2.CONDUCT RESISTANCE : 2 Ω Max
- 3.INSULATION RESISTANCE: 5M Ω Min
- 4.Dielectric test:300V DC

PIN ASSIGNMENT		
P1		OPEN
1	Red	OPEN
2	White	OPEN
3	Green	OPEN
4	Black	OPEN
Shell	Drain+Braid	OPEN